



NOTES:

EACH PWP IS A COMPLETE 4KW SYSTEM WITH 80AMPS OF PV INPUT, A TSW4048 INVERTER / CHARGER AND SWITCHGEAR. THE PARALLEL KIT WIREWAY AT THE BOTTOM ALLOWS 2 OR 3 SYSTEMS TO BE WIRED TOGETHER FOR 8 OR 12KW. THE PWP SYSTEMS ARE WIRED AT THE FACTORY AND SHIPPED IN 4KW MODULES FOR FINAL ASSEMBLY ON SITE.

OPTIONS INCLUDE:

- GROUND FAULT PROTECTION.
- GATEWAY – ONLY 1 REQUIRED PER SYSTEM.
- DC AND/OR AC SURGE PROTECTION.
- GSM CELLULAR MODEM.

SCALE: 1/10



	APOLLO SOLAR 23 F. J. Clarke Circle Bethel, CT 06801 (203) 790-6400 www.Apollo-Solar.com
	PRE-WIRED PANELS PWP 4, 8 & 12KW ASSEMBLIES
11-MAY-2011	J. PFEIFER